

Consumer Preferences in the Used Vehicle Market: Willingness to Pay for Powertrain Type, Driving Range, Vehicle Condition, and Operating Cost

Zain Hoda^{a,1}, Xiatian Iogansen^{a,b,2}, Christina Gore^{b,*,3}, Joshua D. Kneifel^{b,4},
Sindhu Ranganath^{a,b,5} and John Helveston^{a,6}

^aDepartment of Engineering Management and Systems Engineering, George Washington University, Washington D.C., USA

^bApplied Economics Office, Engineering Laboratory, National Institute of Standards and Technology, USA

ARTICLE INFO

Keywords:

Battery electric vehicle
Used vehicle market
Discrete choice experiment
Willingness to pay
Mixed logit
Consumer preferences

ABSTRACT

The discrete choice experiment (DCE) was fielded online to 2,254 US adults planning to buy a used vehicle (Car/SUV) in the next two years, to estimate consumer willingness to pay (WTP) for powertrain type and vehicle attributes in the used-vehicle market in the United States. In the DCE, respondents were presented with repeated choice tasks in which powertrain type (conventional internal combustion engine, gas hybrid electric and battery electric), purchase price, operating cost, driving range, vehicle age, and mileage were systematically varied. Six mixed logit (MXL) models were estimated, stratified first by vehicle segment (car and suv) and then by budget tier (low and high). The results suggest substantial heterogeneity in preferences for battery electric vehicles (BEVs), both within and across segments: mean BEV utility is estimated to be negative and highly significant throughout, but is accompanied by comparatively large standard deviations, a pattern consistent with genuine within-segment polarization rather than uniform aversion. Driving range emerges as the largest positive attribute governing BEV utility, and vehicle age is found to exert a substantial, negative, and monotonic effect on WTP across all segments considered. The only segment and budget combination for which estimated BEV WTP appears to reach statistical parity with an equivalent conventional vehicle is high-budget car buyers considering BEV range over 300 miles per full charge. A complementary comparison of simulated WTP against real-market prices for matched vehicle pairs indicates that observed used-BEV price premiums exceed what our WTP estimates imply is needed for parity with a conventional counterpart in every pair examined, whereas observed HEV price premiums are comparable to, or in one case well below, the WTP-implied premium. These findings may carry implications for used-BEV pricing strategy, resale market development, and the design of consumer incentive programs, though they should be interpreted with the caution warranted by stated-preference data.

1. Introduction

Used vehicles are estimated to constitute approximately 70% of all vehicle transactions in the United States (Bureau of Transportation Statistics, 2023), yet the used-vehicle segment has received comparatively limited systematic attention from researchers or policymakers. This segment appears to represent a distinct buyer population, characterized by different cost constraints, vehicle-quality expectations, and information environments, a distinction taken here to warrant separate empirical treatment.

Research on electric vehicle (EV) consumer preferences has concentrated predominantly on new-vehicle buyers, and the emergence of battery electric vehicles (BEVs) in the secondary market introduces additional complexity that appears worth studying in its own right. Used BEVs matter to the transition beyond their transaction volume. They offer a lower-cost entry point to electric mobility for households that cannot afford a new vehicle (Canepa et al., 2019; Hagman et al., 2016; Sheykhfard et al., 2025). Their expected resale value shapes the economics of new-BEV adoption,

*Corresponding author

¹zain.hoda@gwu.edu, <https://orcid.org/0009-0003-0958-1868>

²xiatian.iogansen@gwu.edu & xiatian.iogansen@nist.gov, <https://orcid.org/0000-0002-4851-1323>

³christina.gore@nist.gov, <https://orcid.org/0000-0002-3586-6918>

⁴joshua.kneifel@nist.gov

⁵sindhu.ranganath@nist.gov, <https://orcid.org/0000-0001-5764-9773>

⁶jph@gwu.edu, <https://orcid.org/0000-0002-2657-9191>

and concern about it (resale anxiety) is a recognised barrier (Brückmann et al., 2021; Lim et al., 2015). Extending the life of vehicles and battery packs may also reduce demand for battery materials and support a circular economy (Consumer Reports, 2023; Guzek et al., 2024; Shaikh et al., 2023)

Consumer demand for used BEVs appears constrained by barriers that extend beyond those documented for the broader EV market. Used BEVs inherit range anxiety, charging-access concerns, and the upfront cost premium common to EVs generally (Sheykhfard et al., 2025) but buyers also cannot observe the condition of a used vehicle directly. Uncertainty about prior condition and reliability is reported to be a primary purchase deterrent (Fernandes, 2023), and because battery aging is not captured by age or odometer readings alone (Prieto et al., 2015), those two attributes may have to carry more of the discount for a used BEV than for a conventional vehicle.

Understanding the determinants of used-BEV purchase decisions is therefore considered important for policymakers, manufacturers, dealers, and researchers seeking to support the transition to electric mobility through the secondary vehicle market. This study reports quantitative estimates of willingness to pay (WTP) for powertrain type in the used vehicle market in the United States, disaggregated by consumer budget, vehicle type, driving range, and vehicle age. Each respondent evaluated six sets of three hypothetical used vehicles, which differed in fuel type, price, running cost, range, model year and odometer reading. Each set also included an option to buy none of them. From these choices we recover the implicit dollar value of each attribute.

Two dimensions are used to structure the analysis, each motivated by heterogeneity documented in the used-vehicle market. Car and SUV buyers are understood to operate in different price ranges, to have different range requirements, and to face different operating-cost profiles; pooling them risks masking preference structures that may diverge precisely on the attributes most consequential for BEV adoption. Budget tier is thought to determine which vehicles fall within a buyer's realistic consideration set and to modulate price sensitivity: lower-budget buyers in the used market appear to face fewer BEV options and to bear higher relative cost burdens (Konstantinou et al., 2025; Loh and Noland, 2024), suggesting that the price-range interaction warrants first-order attention.

This study addresses two interrelated research questions:

1. How do consumer willingness-to-pay estimates for used-vehicle attributes (powertrain type, driving range, vehicle age, mileage, and operating cost) appear to compare across vehicle segment and budget tier?
2. How do existing used BEVs appear to compete against their conventional or hybrid counterparts as vehicles age?

The remainder of the paper is organized as follows. Section 2 reviews the relevant literature on used-vehicle markets, general EV adoption determinants, and consumer preferences in the used-EV segment specifically. Section 3 describes the survey design, data collection, and sample profile. Section 4 presents the statistical methods employed. Section 5 reports the mixed logit estimates, Section 6 analyzes their implications for willingness to pay and market competitiveness, Section 7 discusses policy implications, and Section 8 is the conclusion.

2. Literature Review

The review that follows draws on three overlapping bodies of work: the broader used-vehicle market, general EV adoption determinants, and the emerging literature specific to used-EV consumer preferences.

2.1. The Broader Used-Vehicle Market

Affordability, vehicle condition, and reliability appear to be the dominant purchase criteria for used-vehicle buyers (Consumer Reports, 2023; U.S. Environmental Protection Agency, 2023). Fuel costs are also reported to factor into vehicle choice, particularly among cost-sensitive households. Used-car purchasing is reported to be more common among larger households and renters; low-income single-vehicle renters are found to carry the highest vehicle-cost burdens relative to income (Konstantinou et al., 2025).

These burdens appear to have grown since 2020. Average used-vehicle prices are reported to have climbed relative to pre-pandemic levels and have remained elevated through 2024–2025 (Cox Automotive, 2024); in April 2025, the average transaction price was \$25,547 (Kelley Blue Book, 2025). Cox Automotive (2025) report that 74% of used-vehicle buyers evaluated both new and used options, and that 71% entered the market without a fixed vehicle preference, which may indicate that buyers are searching more broadly under price pressure. C-4 Analytics (2025) report that 43% of consumers would switch brands to obtain a lower price.

2.2. General Factors in EV Adoption

Purchase price, operating costs, driving range, recharging time, charging infrastructure, environmental benefits, and government incentives have all been found to shape EV adoption decisions (Zou et al., 2020). Range and recharging time are reported to show statistically significant effects across multiple stated-preference studies (Liao et al., 2017). Pooled evidence suggests that the range–charging trade-off only appears at higher range: consumers appear willing to accept shorter range in exchange for denser charging networks only once BEV range already exceeds roughly 250–300 km (Rosales-Tristancho et al., 2024). Below that threshold, additional charging infrastructure does not appear to compensate for range loss, a finding that may be particularly relevant for used EVs, where buyers could plausibly discount perceived range due to battery aging. Battery warranty and depreciation rate are also reported to independently affect purchase intent (Li et al., 2020).

2.3. Used Electric Vehicle Adoption

The U.S. used-EV market is reported to have passed 400,000 units in 2023, yet studies of consumer preferences in that market remain sparse (Moras et al., 2025). Most existing work assumes price sensitivity to be the primary driver and treats it as approximately uniform across buyers. Moras et al. (2025) instead identify three distinct segments among prospective used-EV buyers: those for whom cost appears to be a binding constraint, those apprehensive about adapting to EV technology, and those apparently drawn by a favorable cost-benefit ratio and lower depreciation risk. These segments appear to share a price orientation but to arrive at it through different reasoning.

Current used EV owners look much like early adopters of new EVs, they are disproportionately male, middle-aged, highly educated, and higher-income (Sk. Md. Mashrur, 2024; Wei San Loh, 2024). Full-time employment and private off-street parking are also reported to predict ownership (Sk. Md. Mashrur, 2024). This suggests that the used market has not yet substantially reached different or lower-income buyer segments.

Prior to purchase, used-EV buyers are reported to cite price, battery performance, and charging access as their principal concerns (Loh and Noland, 2024). Lower-income buyers appear more sensitive to both price and charging availability than higher-income buyers (Loh and Noland, 2024), and concern about infrastructure is reported to correlate with outright reluctance to buy (Sk. Md. Mashrur, 2024). Prior EV ownership appears to work in the opposite direction: experienced EV drivers are reported to be more comfortable purchasing pre-owned vehicles, and new EV drivers report that they would consider a used EV once range and home-charging needs are met (Mashrur and Mohamed, 2025).

Used vehicle and new vehicle buyers show broadly similar EV preference structures, with three differences. Used-vehicle buyers are reported to be more sensitive to fast-charging time and to the proximity of charging infrastructure to home (Zou et al., 2020). They are less likely to have access to lease pathways. And they are less likely to have larger purchase incentives or the home-charging setups that new-EV buyers may take for granted. On price, average used-EV prices are reported to range from \$9,000–\$37,000 depending on range and vehicle class, against roughly \$14,000 for a comparable used gasoline vehicle (Konstantinou et al., 2025), a gap that price incentives may need to help close.

2.4. Synthesis and Research Gap

Used-car buyers appear more cost-conscious than new-car buyers, and current market conditions appear to have widened that difference. Price is reported to drive used-EV interest, yet buyers in that market do not appear to be a uniform group: their motivations, income, and infrastructure access differ, as does the weight they appear to assign to battery performance, range, and charging. Battery warranty and depreciation rate are reported to shape decisions beyond sticker price alone.

Existing studies draw predominantly on convenience samples or current owners, which may limit generalizability to prospective buyers. Few examine how preference weights shift across income groups, housing types, or vehicle-ownership contexts within the used-vehicle segment specifically. This study is intended to address that gap through a discrete choice experiment that estimates willingness to pay for powertrain type, driving range, vehicle age, operating cost, and purchase price across a nationally distributed sample of prospective used-vehicle buyers, disaggregated by vehicle segment and budget tier.

3. Survey Design, Data Collection, and Sample Profile

3.1. Vehicle Choice Experiment

Screening admitted U.S. adults who planned to acquire a used car (sedan or hatchback) or SUV (including crossovers) within two years. Each respondent completed six choice tasks. In each task they saw three used vehicles and could decline all of them (a “None of the above” option)

To keep the choice tasks realistic, price and attribute levels were calibrated to each respondent’s segment. Respondents were routed to one of four designs: car or SUV, crossed with a low or high budget (see Table 1). The DCE attributes are mileage, powertrain type, electric driving range, operating cost, model year, and purchase price. The DCE included three powertrain types: conventional gas vehicles (ICEV), gas hybrid electric vehicles (HEV), and battery electric vehicles (BEV) with varying driving ranges for BEV alternatives. Prior evidence identifies age and mileage as primary determinants of used-vehicle value (Prieto et al., 2015); both are accordingly included in the design, with model year serving as the observable proxy for vehicle age.

Operating cost levels were derived from observed fuel-economy data. Vehicle energy consumption (in kWh per mile for BEVs and miles per gallon for ICEVs and HEVs) was sourced from EPA ratings for 2024 model-year vehicles, stratified by powertrain and body type. These figures were combined with the 10th–90th percentile range of state-level electricity rates (\$0.11–\$0.33 per kWh) and retail gasoline prices (\$2.66–\$4.77 per gallon) prevailing in early 2025 to produce 20 approximately equally spaced operating-cost values per powertrain–body-type combination. Costs were displayed to respondents in cents per mile alongside the miles-per-gallon equivalent of a conventional gasoline vehicle at the same cost, intended to allow direct comparison across powertrain types. Operating cost was bounded by powertrain type: ICEV profiles were limited to 9–18 cents per mile, BEV profiles to 3–12 cents per mile, and HEV profiles to 6–12 cents per mile for car alternatives and 9–18 cents per mile for SUV alternatives, reflecting plausible fuel-cost ranges for each powertrain. Choice sets were drawn at random from the restricted profile space, with alternatives balanced across powertrain types and dominated profiles excluded.

Profiles were drawn at random from the restricted profile space using the `cbcTools` R package (Helveston, 2025), with the powertrain-specific operating-cost bounds described above. Table 1 defines every attribute and lists its levels, and Figure 1 shows an example choice task.

Before the DCE, respondents reported their vehicle budget. To prevent styling from confounding attribute effects, each respondent also chose one image, from nine options within their selected body type, closest to the next vehicle they were considering. That image depicted all alternatives in every choice task.

Table 1
BEV choice experiment attributes and levels.

Attribute	Definition	Levels			
		Low-budget Car (≤\$20,000)	High-budget Car (>\$20,000)	Low-budget SUV (≤\$25,000)	High-budget SUV (>\$25,000)
Mileage	The total number of miles a vehicle has traveled since manufacture.	All levels: 20,000–60,000 miles (5000-mile increments).			
Powertrain	The type of powertrain the vehicle runs on.	All levels: (1) <i>Conventional</i> : Gasoline or other liquid-fuel engine, such as diesel or flex-fuel. (2) <i>Gas hybrid electric vehicle (HEV)</i> : Smaller gasoline engine + electric motor + small battery. The gasoline engine recharges the battery to improve fuel efficiency. (3) <i>Battery electric vehicle (BEV)</i> : Electric motor only. Must be plugged into an electrical outlet to be refueled.			
Electric Range	Maximum distance the BEVs can travel on a full charge. Applies to BEVs only.	50–150 miles (50-mile increments)	100–250 miles (50-mile increments)	150–250 miles (50-mile increments)	200–350 miles (50-mile increments)
Operating Cost	Cost in cents per mile driven of fueling the vehicle. The equivalent fuel efficiency in miles per gallon (MPG) of a conventional gasoline vehicle is displayed in parenthesis.	Car: ICEV: 9–18 cents/mile HEV: 6–12 cents/mile BEV: 3–12 cents/mile		SUV: ICEV: 9–18 cents/mile HEV: 9–18 cents/mile BEV: 3–12 cents/mile	
Model Year	The actual year the vehicle was made.	All levels: 2015–2023 (2-year increments).			
Purchase price	The total cost of the vehicle in dollars, including down payment, monthly payments, taxes, and fees.	\$10,000–\$20,000 (\$2,000 increments)	\$20,000–\$40,000 (\$5,000 increments)	\$15,000–\$25,000 (\$5,000 increments)	\$25,000–\$45,000 (\$5,000 increments)

Question 1 of 6

Assume you are able to purchase a vehicle that looks like the one you selected (see photo). Which of the following versions of that vehicle would you be most likely to purchase? Please compare the key features shown for each option before making your selection.



If these were your only options, which would you choose?

Option 1	Option 2	Option 3	Option 4
<u>Purchase price:</u> \$ 40,000	<u>Purchase price:</u> \$ 45,000	<u>Purchase price:</u> \$ 40,000	Even if these were my best options, I would not choose any of these vehicles
<u>Powertrain:</u> Conventional	<u>Powertrain:</u> Gas hybrid	<u>Powertrain:</u> Battery electric 200 miles on a full charge	
<u>Model year:</u> 2019	<u>Model year:</u> 2023	<u>Model year:</u> 2023	
<u>Mileage:</u> 20,000	<u>Mileage:</u> 25,000	<u>Mileage:</u> 25,000	
<u>Operating cost:</u> 15 cents per mile (25.7 MPG equivalent)	<u>Operating cost:</u> 9 cents per mile (37.9 MPG equivalent)	<u>Operating cost:</u> 9 cents per mile (37.2 MPG equivalent)	

Figure 1: Example of a vehicle choice task presented to respondents. Each task offers three used vehicle alternatives with varying attributes and a “None of the above” opt-out option.

3.2. Data Collection and Sample Profile

Online surveys ran in batches from December 2025 to April 2026 on two panels, Dynata and Prolific, with participants compensated on completion (median duration approximately 14 minutes). Of 2,991 completed records, those that failed attention checks, contradicted themselves across sections, or gave incoherent open-ended text were dropped, leaving a final analytic sample of 2,254 respondents.

Compared with ACS 2020–2024 five-year estimates (Table 2), the sample is younger, more female, better educated, and more renter-heavy, and under-represents households earning \$150,000 or more (13.5% vs. 20%). This pattern is broadly consistent with online-panel recruitment and with the focus on used-vehicle buyers, while the middle income brackets approximate the national profile.

Table 2

Sample profile compared with the U.S. population (ACS 2020–2024 5-year estimates).

	Sample (n)	Sample (%)	ACS (%)
<i>Age</i>			
18 - 24	329	14.7	11.7
25 - 34	675	30.2	17.5
35 - 44	574	25.7	16.9
45 - 54	344	15.4	15.6
55 - 64	190	8.5	16.2
65+	121	5.4	22.0
<i>Gender</i>			
Female	1,340	59.6	51.0
Male	861	38.3	49.0
Other	49	2.2	–
<i>Race</i>			
White alone	1,543	68.5	63.3
Black or African American alone	322	14.3	11.9
Other or multiple races	389	17.3	24.8
<i>Hispanic origin</i>			
Hispanic or Latino	269	11.9	17.4
Not Hispanic or Latino	1,985	88.1	82.6
<i>Household income</i>			
Less than \$25,000	343	15.2	14.6
\$25,000 - \$49,999	374	16.6	16.7
\$50,000 - \$74,999	545	24.2	15.5
\$75,000 - \$99,999	257	11.4	12.6
\$100,000 - \$149,999	428	19.0	17.5
\$150,000 or more	304	13.5	23.0
<i>Education</i>			
High school or less	314	14.0	36.4
Some college or associate	731	32.5	27.9
Bachelor's degree	765	34.0	21.6
Graduate or professional degree	438	19.5	14.1
<i>Housing tenure</i>			
Own	1,087	52.0	65.2
Rent	1,002	48.0	34.8
<i>Housing type</i>			
Single-family detached	1,367	60.6	62.3
Single-family attached	227	10.1	6.4
Apartment (2+ units)	574	25.5	26.0
Mobile home or other	86	3.8	5.2

Notes: Sample size and shares are unweighted and exclude item nonresponse. '–' indicates no comparable ACS category. ACS universes: population 18+ (age, gender, race, Hispanic origin), population 25+ (education), and households (income, tenure, housing type).

3.3. Household Vehicle Context and Used-BEV Purchase Interest

Table 3 profiles the households behind the sample: fleet size, primary-vehicle powertrain, home-charger access, neighbor EV ownership, and stated likelihood of buying a used BEV as the next vehicle. Most respondents' households appear to own at least one vehicle: 35.2% report one vehicle and 37.9% report two, while 4.0% report owning none. Among respondents reporting a current primary household vehicle, a large majority (83.8%) report driving a conventional gasoline vehicle, with hybrids (10.2%), battery electric vehicles (4.1%), and plug-in hybrids (1.8%) comprising the remainder, a distribution consistent with the sample's focus on prospective used-vehicle buyers rather than existing EV owners. Home-charger access appears split roughly evenly, with 44.0% reporting access to a home charger and 49.1% reporting none. A comparable share of respondents report knowing a neighbor who owns an EV (39.8%) as report not knowing one (31.9%), with 28.3% unsure. Stated likelihood of purchasing a used BEV as the next vehicle appears concentrated at the unlikely end of the scale: 34.3% report being very unlikely and 20.8% somewhat unlikely to do so, compared with 8.5% very likely and 22.8% somewhat likely, with the remaining 13.6% neutral. These measures characterize the sample's baseline exposure to and stated receptivity toward BEVs, alongside the vehicle segment and budget tier stratification used in Sections 5.1 and 6.1.

Table 3

Household vehicle context and used-BEV purchase interest.

	n	%
<i>Household vehicle count</i>		
0	91	4.0
1	793	35.2
2	854	37.9
3	292	13.0
4 or more	223	9.9
<i>Current primary vehicle fuel type</i>		
Gasoline (ICEV)	1,153	83.8
Hybrid (HEV)	140	10.2
Plug-in hybrid (PHEV)	25	1.8
Battery electric (BEV)	57	4.1
Other	1	0.1
<i>Home charger access</i>		
Yes	992	44.0
No	1,106	49.1
Not sure	154	6.8
<i>Knows a neighbor who owns an EV</i>		
Yes	896	39.8
No	718	31.9
Not sure	638	28.3
<i>Likelihood of purchasing a used BEV next</i>		
Very unlikely	773	34.3
Somewhat unlikely	469	20.8
Neutral	307	13.6
Somewhat likely	514	22.8
Very likely	191	8.5

Notes: n = 2,254 unless otherwise noted; percentages exclude item nonresponse. Current primary vehicle fuel type was asked only of respondents reporting a current household vehicle (n = 1,376); all other items were asked of the full analytic sample.

4. Method

4.1. Mixed Logit Models

Consumer choice is modeled within the random utility framework. Each respondent i is assumed to select the alternative j that maximizes latent utility U_{ij} in each choice task, where utility is specified as a linear function of

observed vehicle attributes augmented by an unobserved idiosyncratic error term assumed to follow an independent Gumbel distribution.

Two features of the choice setting favor a mixed logit (MXL) over a baseline multinomial logit (MNL). First, a consumer who prefers a conventional ICEV would, if that option were unavailable, plausibly switch to an HEV more readily than to a BEV, because the two share a combustion engine and a familiar refueling experience. The MNL's proportional-substitution property (IIA) rules this out. Second, the MNL assumes homogeneous preferences, which is hard to reconcile with the polarization in EV attitudes and is rejected here by significant standard-deviation parameters $\hat{\sigma}_k$ across virtually all attributes in all models. The MXL addresses both concerns by modeling each preference parameter as a draw from a normal mixing distribution (**mcfaddenMixedMNLModels2000; trainDiscreteChoiceMethods2009**):

$$\beta_{ik} \sim \mathcal{N}(\mu_k, \sigma_k^2) \quad (1)$$

where μ_k is the population mean valuation for attribute k and σ_k captures the estimated dispersion of that valuation across respondents. A statistically significant $\hat{\sigma}_k$ is interpreted as evidence that preferences for attribute k are genuinely heterogeneous in the population, rather than uniform. The seven parameters specified as randomly distributed are the BEV powertrain indicator, HEV powertrain indicator, BEV driving range, vehicle mileage, vehicle age, operating cost, and the alternative-specific constant for the no-choice (opt-out) option. Purchase price enters as the scale parameter λ_i in the WTP-space reparameterization rather than as a randomly distributed preference weight. The internal combustion engine vehicle (ICEV) serves as the reference powertrain category throughout.

Following Helveston (2023), the models are specified directly in WTP space by reparameterizing the utility function as:

$$U_{ij} = \lambda_i \left(\sum_k \omega_{ik} x_{ijk} - p_{ij} \right) + \varepsilon_{ij} \quad (2)$$

where $\lambda_i > 0$ is a respondent-specific price-sensitivity (scale) parameter and ω_{ik} is respondent i 's marginal WTP for attribute k in dollars. Because the dollar value of each attribute is itself the estimated parameter, each ω_{ik} has its own normal distribution $\mathcal{N}(\mu_{\omega_k}, \sigma_{\omega_k}^2)$ across respondents, and the population mean WTP is read directly from $\hat{\mu}_{\omega_k}$ with no division by the price coefficient. Uncertainty bounds come from 10,000 draws from the estimated joint parameter distribution (95% confidence interval).

Six MXL models are estimated: two vehicle-segment models (car and SUV) and four budget-tier models (car and SUV, each crossed with low and high budget). Estimation uses the `logitr` package (Helveston, 2023) with respondent-clustered likelihoods to handle the six repeated choices each respondent contributes. The simulated likelihood is evaluated with 5,000 Sobol quasi-random draws per respondent.

4.2. WTP for Defined Vehicle Profiles

While WTP-space estimation yields interpretable marginal valuations for each attribute, reporting coefficients in isolation is arguably too abstract for meaningful powertrain-type comparisons. A consumer choosing between a used BEV and an equivalent ICEV is unlikely to weigh powertrain type and driving range as separate, independent attributes, since range is a property specific to the BEV that does not apply to the ICEV baseline. Reporting the BEV powertrain coefficient in isolation would correspond to WTP for a BEV with zero driving range, a configuration that is not economically meaningful. To produce more readily interpretable figures, BEV WTP is therefore computed for specific vehicle configurations by combining the powertrain, range, and age parameters:

$$\text{WTP}_{\text{BEV}}(r, a) = \hat{\mu}_{\omega_{\text{BEV}}} + \hat{\mu}_{\omega_{\text{range}}} \cdot r + \hat{\mu}_{\omega_{\text{age}}} \cdot a \quad (3)$$

where r is driving range in hundreds of miles and a is vehicle age in years. This quantity is interpreted as the dollar premium (positive) or required discount (negative) for a consumer to be indifferent between a BEV with range r and age a and an otherwise identical ICEV. Sections 6.1 and 6.2 present this combined WTP at fixed combinations of range (100, 200, and 300 miles) and vehicle age. Uncertainty is propagated by drawing 10,000 samples from the estimated joint parameter distribution and reporting 95% simulation intervals.

1 **5. Results**

2 **5.1. Mixed Logit Estimates: Preference Heterogeneity by Subgroup**

3 Table 4 reports the full MXL parameter estimates for the six models, stratified by vehicle segment (car, suv) and by
4 budget tier within segment (car low, car high, suv low, suv high). For each attribute, the population mean coefficient ($\hat{\mu}$)
5 and the estimated standard deviation of the mixing distribution ($|\hat{\sigma}|$) are reported, both expressed in \$1,000 WTP-space
6 units. A statistically significant $|\hat{\sigma}|$ is taken as evidence of genuine preference heterogeneity for that attribute within
7 the subgroup. Model fit statistics are reported at the base of the table.

Table 4
Mixed logit model estimates in WTP space: by vehicle type and budget subgroups.

	By Vehicle Type		By Budget			
	Car	SUV	Car (Low)	Car (High)	SUV (Low)	SUV (High)
Mean parameters						
λ (scale)	0.173 (0.006)***	0.136 (0.004)***	0.364 (0.013)***	0.122 (0.006)***	0.245 (0.012)***	0.121 (0.005)***
BEV powertrain	-17.359 (1.209)***	-26.105 (1.935)***	-10.375 (0.820)***	-18.325 (2.681)***	-20.485 (1.982)***	-22.304 (2.906)***
HEV powertrain	0.603 (0.473)	0.805 (0.553)	-0.577 (0.322)	4.240 (1.005)***	-0.731 (0.502)	2.271 (0.811)**
Electric range	4.353 (0.642)***	4.708 (0.621)***	2.218 (0.568)***	5.234 (1.190)***	4.100 (0.784)***	3.536 (0.924)***
Mileage	-2.019 (0.122)***	-3.015 (0.165)***	-1.003 (0.078)***	-3.136 (0.272)***	-1.484 (0.139)***	-3.848 (0.248)***
Vehicle age	-0.826 (0.069)***	-1.450 (0.094)***	-0.279 (0.043)***	-1.919 (0.175)***	-0.436 (0.074)***	-2.174 (0.150)***
Operating cost	-0.746 (0.051)***	-0.861 (0.059)***	-0.412 (0.033)***	-1.054 (0.114)***	-0.581 (0.053)***	-0.900 (0.085)***
No choice	-57.452 (1.436)***	-74.663 (1.736)***	-33.136 (0.851)***	-77.831 (3.143)***	-46.547 (1.523)***	-84.371 (2.442)***
Standard deviation						
$ \hat{\sigma} $: BEV powertrain	17.017 (0.989)***	22.872 (1.172)***	9.498 (0.657)***	21.769 (2.119)***	14.543 (1.135)***	22.269 (2.211)***
$ \hat{\sigma} $: HEV powertrain	9.846 (0.546)***	12.386 (0.685)***	5.518 (0.339)***	11.557 (1.194)***	7.254 (0.594)***	14.049 (1.006)***
$ \hat{\sigma} $: Electric range	4.352 (0.907)***	0.924 (1.963)	1.897 (1.312)	6.534 (1.369)***	0.416 (1.632)	3.803 (1.255)**
$ \hat{\sigma} $: Mileage	1.381 (0.174)***	2.027 (0.214)***	0.770 (0.103)***	1.683 (0.425)***	1.091 (0.183)***	2.292 (0.302)***
$ \hat{\sigma} $: Vehicle age	0.958 (0.103)***	1.300 (0.132)***	0.430 (0.066)***	1.690 (0.215)***	0.469 (0.137)***	1.772 (0.180)***
$ \hat{\sigma} $: Operating cost	0.550 (0.066)***	0.745 (0.069)***	0.308 (0.037)***	0.693 (0.149)***	0.425 (0.061)***	0.851 (0.092)***
$ \hat{\sigma} $: No choice	13.665 (1.009)***	15.965 (1.212)***	5.152 (0.704)***	17.317 (2.153)***	8.669 (1.157)***	15.539 (1.775)***
Respondents	1,099	1,155	657	442	441	714
Choice observations	6,594	6,930	3,942	2,652	2,646	4,284
Log-Likelihood	-6,765.38	-7,198.68	-3,758.26	-2,726.13	-2,621.49	-4,448.01
Null Log-Likelihood	-9,141.23	-9,607.02	-5,464.77	-3,676.45	-3,668.13	-5,938.89
AIC	13,560.76	14,427.37	7,546.52	5,482.26	5,272.97	8,926.02
BIC	13,662.66	14,530.02	7,640.71	5,570.50	5,361.18	9,021.46
McFadden R^2	0.2599	0.2507	0.3123	0.2585	0.2853	0.2510
Adj. McFadden R^2	0.2583	0.2491	0.3095	0.2544	0.2812	0.2485

Notes: mean and standard-deviation coefficients in \$1,000 units, denominated per natural attribute unit: powertrain indicators and the no-choice constant per 1 (dummy); electric range per 100 miles; mileage per 10,000 miles; vehicle age per 1 year; operating cost per 1 cent/mile. The scale parameter λ is not a dollar-denominated WTP coefficient. Significance codes: $p < 0.001$ '***' $p < 0.01$ '**' $p < 0.05$ '*' $p < 0.1$ '.' Standard errors in parentheses.

The sign and significance pattern of the mean coefficients appears remarkably consistent across all six specifications. BEV powertrain utility is negative and highly significant in every specification ($\hat{\mu} = -10.375$ to -26.105 , $p < 0.001$ throughout), more negative for SUV buyers than car buyers at every budget tier, and more negative for high-budget than low-budget buyers within the car segment ($\hat{\mu} = -18.325$ vs. -10.375); the budget gradient appears comparatively muted within the SUV segment ($\hat{\mu} = -22.304$ vs. -20.485). HEV powertrains appear to follow a different pattern: statistically indistinguishable from the conventional baseline among low-budget buyers in both segments, but carrying a significant premium among high-budget buyers (car high: $\hat{\mu} = 4.240$, $p < 0.001$; SUV high: $\hat{\mu} = 2.271$, $p < 0.01$), suggesting that hybrid acceptance concentrates in the higher-budget market rather than being distributed evenly. Electric driving range is positive and significant in all six models, and mileage, vehicle age, and operating cost are negative and significant in all six, with each attribute's magnitude scaling consistently with both budget tier (larger for high-budget buyers) and vehicle segment (larger for SUV than car buyers). Model fit appears comparable across specifications (McFadden $R^2 = 0.251$ – 0.312), with the strongest fit obtained for the low-budget car model. Section 6.1 translates these coefficients, already expressed in WTP space, into the dollar-denominated valuations reported in Figure 2.

Dispersion is largest for powertrain.BEV and HEV powertrain coefficients carry large, statistically significant standard deviations in all six models ($|\hat{\sigma}|_{\text{BEV}} = 9.498$ – 22.872 ; $|\hat{\sigma}|_{\text{HEV}} = 5.518$ – 14.049 ; $p < 0.001$ throughout), which is consistent with the negative mean BEV valuation coexisting with a meaningful share of respondents holding substantially more favorable views within every segment and budget tier. Mileage, age, and operating-cost heterogeneity is likewise significant in every subgroup. Driving range shows a less consistent pattern: heterogeneity is significant for car buyers overall ($|\hat{\sigma}| = 4.352$, $p < 0.001$) and for high-budget car buyers specifically ($|\hat{\sigma}| = 6.534$, $p < 0.001$), and for high-budget SUV buyers ($|\hat{\sigma}| = 3.803$, $p < 0.01$), but is not statistically distinguishable from zero for low-budget car buyers, low-budget SUV buyers, or SUV buyers overall, suggesting that range preferences may be comparatively homogeneous within those three subgroups, in contrast to the significant dispersion found for every other attribute throughout the table. Sections 6.1 and 6.2 build on these mean estimates to quantify what the coefficients may imply in dollar terms and for real-vehicle market competitiveness, respectively.

6. Analysis

6.1. Q1 – How Do Preferences for Vehicle Attributes Appear to Compare?

Figure 2 summarizes estimated willingness to pay for each vehicle attribute, disaggregated by vehicle segment (car, SUV) and budget tier (low, high budget); error bars represent 95% confidence intervals around the mean WTP estimates, and heterogeneity in preferences across individuals is not depicted. For the three BEV configurations (100, 200, and 300 miles of range), solid error bars denote WTP calculated at range levels falling within the range shown to that segment in the choice experiment, whereas dotted error bars denote WTP extrapolated to range levels outside that segment's design space and are accordingly interpreted with greater caution. The figure axis is scaled in thousands of dollars for readability; dollar figures below are reported at full precision. For powertrain type, high-budget buyers appear to place a statistically significant premium on HEVs relative to the conventional gasoline baseline: approximately \$4,200 among car buyers and \$2,300 among SUV buyers. Low-budget buyers, by contrast, show no significant HEV premium in either segment, with the car-segment estimate only marginally negative (approximately -\$600). BEV powertrains carry a WTP penalty relative to conventional vehicles in every segment and budget combination considered, though this penalty appears to narrow sharply as driving range increases. At 100 miles of range, WTP for a BEV is approximately -\$13,100 among high-budget car buyers, -\$8,200 among low-budget car buyers, -\$18,800 among high-budget SUV buyers, and -\$16,400 among low-budget SUV buyers. Extending range to 300 miles closes most of this gap: WTP rises to approximately -\$2,600 (high-budget car, with a confidence interval spanning zero), -\$3,700 (low-budget car), -\$11,700 (high-budget SUV), and -\$8,200 (low-budget SUV). The 300-mile car result for high-budget buyers is the only combination in the figure for which BEV WTP is not statistically distinguishable from the conventional baseline, which may identify added range as a particularly effective lever for closing the BEV valuation gap among higher-budget car buyers.

Vehicle age, mileage, and operating cost are each valued negatively across all four subgroups, and each penalty appears to scale consistently with budget tier: high-budget buyers exhibit larger dollar-denominated penalties than low-budget buyers for the same attribute in both segments. Mileage appears to carry the largest of the three penalties throughout, ranging from approximately -\$1,000 (low-budget car) to -\$3,100 (high-budget car), and from -\$1,500 (low-budget SUV) to -\$3,800 (high-budget SUV). Vehicle age WTP ranges from approximately -\$300 (low-budget car) to

1 -\$1,900 (high-budget car), and from -\$400 (low-budget SUV) to -\$2,200 (high-budget SUV). Operating cost appears
2 smaller than both throughout, ranging from approximately -\$400 (low-budget car) to -\$1,100 (high-budget car), and
3 from -\$600 (low-budget SUV) to -\$900 (high-budget SUV), and is overtaken by the age penalty among high-budget
4 buyers in both segments. This pattern – larger dollar penalties among higher-budget buyers – appears to mirror the
5 overall scale of WTP in each subgroup rather than reflecting a qualitatively different preference structure.

6 Comparing across vehicle segments, SUV buyers exhibit systematically larger BEV, mileage, and age penalties
7 than car buyers at the same budget tier; operating-cost penalties appear to follow the same pattern among low-budget
8 buyers, but reverse among high-budget buyers, where the car penalty is larger (-\$1,100 vs. -\$900). HEV premiums
9 appear smaller for SUV buyers than for car buyers among high-budget respondents. Together, these patterns suggest
10 that BEV valuation gaps are narrowest, and closest to parity with conventional vehicles, among higher-budget car
11 buyers purchasing longer-range vehicles, a reading consistent with the preference structure reported in Table 4.




Figure 2: Willingness to pay for vehicle attributes, by vehicle segment and budget tier (95% confidence intervals shown; values in thousands of dollars). For the BEV range configurations, solid intervals mark WTP calculated within the range shown to that segment and dotted intervals mark WTP extrapolated beyond it.

6.2. Q2 – How Do Existing Used BEVs Appear to Compete Against Their Conventional Counterparts?

Figure 3 and Figure 4 translate the attribute-level WTP estimates in Section 6.1 into a head-to-head comparison against real, currently marketed vehicles, following the logic of Helveston et al. (2014) that competitiveness is set by a vehicle's full attribute bundle relative to a specific counterpart rather than by powertrain type considered in isolation. Matched pairs of real vehicles sharing a common conventional (CV) counterpart were identified, subject to a minimum of 200 real used-market listings between 2.5 and 3.5 years of vehicle age; three BEV-versus-CV pairs (high-budget car, low-budget car, low-budget SUV) and two HEV-versus-CV pairs (high-budget car, high-budget SUV) met this threshold, while no BEV pair was available for the high-budget SUV segment and no HEV pair was available in either low-budget segment. For each retained pair, real used-market listings were used to compute the mean transaction price of the powertrain-of-interest and of its CV counterpart at approximately three years of age, yielding an observed mean price premium (or discount). Separately, the vehicle-segment- and budget-tier-matched MXL model (with a 20% buffer) from Table 4 was used to predict WTP for the same vehicle at the same age: the powertrain coefficient, driving range (depreciated at an assumed 5% annual rate to three years, where applicable), and the operating-cost differential implied by each powertrain's typical fuel-cost profile are summed to obtain a simulated Net WTP, with 95% simulation intervals obtained by drawing 10,000 samples from the estimated joint parameter distribution. Plotting the cumulative attribute contributions (bars) alongside simulated Net WTP (point and interval) and the observed real-market price premium (dashed line) in the same figure allows what consumers say they would pay to be compared directly against what the market currently charges.

For BEV-versus-CV pairs (Figure 3), the powertrain penalty is the dominant negative contributor throughout (-\$10,375 to -\$20,485), partially offset by the positive contribution of driving range (+\$2,852 to +\$11,219, reflecting each vehicle's specific range depreciated to three years) and a small positive operating-cost contribution (+\$371 to +\$949); simulated Net WTP is negative for all three pairs, ranging from -\$6,150 (high-budget car) to -\$10,897 (low-budget SUV). In every pair, the observed real-market price premium sits well above the simulated Net WTP, indicating that current used-BEV pricing has not adjusted to reflect the discount our estimates imply consumers require for indifference with the conventional counterpart. The gap is narrowest for the high-budget car pair, where the BEV is priced at approximately parity with its CV counterpart (-\$68 mean premium) against a simulated Net WTP of -\$6,150, a roughly \$6,100 shortfall. The gap is far larger for the two lower-budget pairs: the low-budget car BEV carries an observed price premium of +\$8,585 against a simulated Net WTP of -\$7,152 (a difference of roughly \$15,700), and the low-budget SUV BEV carries an observed premium of +\$5,962 against a simulated Net WTP of -\$10,897 (a difference of roughly \$16,900). Rather than being priced at a discount to compensate for lower range and the BEV penalty, the two lower-budget BEVs are in fact priced at a premium over their CV counterparts in the real market – the opposite of what the WTP estimates would imply is needed for competitiveness.

HEV-versus-CV pairs (Figure 4) show a more mixed relationship between simulated WTP and observed pricing. In the high-budget car segment, simulated Net WTP (+\$4,860) exceeds the observed price premium (+\$1,945), suggesting that this HEV's real-market pricing has not yet captured the full premium consumers say they would accept – the vehicle appears underpriced relative to consumer valuation. In the high-budget SUV segment, the relationship reverses: the observed price premium (+\$7,987) substantially exceeds simulated Net WTP (+\$2,809), a gap of roughly \$5,200 that our attribute-based estimates cannot account for and that plausibly reflects reliability reputation, resale-value expectations, or other brand-specific factors not captured by the DCE attributes.




Figure 3: Willingness-to-pay decomposition (powertrain, driving range, and operating cost) for real, currently marketed BEV vehicles relative to each vehicle's closest conventional counterpart, by vehicle segment and budget tier. The blue point/error bar is simulated Net WTP (mean, 95% interval); the dashed red line is the observed mean real-market price premium (or discount) at approximately three years of age. No matched BEV pair meeting the sample-size threshold was available for the high-budget SUV segment.




Figure 4: Willingness-to-pay decomposition (powertrain and operating cost) for real, currently marketed HEV vehicles relative to each vehicle's closest conventional counterpart, by vehicle segment and budget tier. The blue point/error bar is simulated Net WTP (mean, 95% interval); the dashed red line is the observed mean real-market price premium at approximately three years of age. No matched HEV pair meeting the sample-size threshold was available in either low-budget segment.

7. Discussion: Policy Interventions in Light of the Estimates

Most U.S. incentives for electric-vehicle adoption were designed around the new-vehicle market. The federal clean vehicle credit (Internal Revenue Code §30D) has long offered up to \$7,500 toward a qualifying new EV, and a used-vehicle counterpart arrived only in 2023, with the introduction of the used clean vehicle credit (§25E): the lesser of \$4,000 or 30% of the sale price, limited to vehicles priced at or below \$25,000 and to buyers below set income thresholds, and transferable to the dealer as a point-of-sale discount since 2024. State programs, from California's Clean Vehicle Rebate Project to scrappage-and-replacement schemes such as Clean Cars 4 All, follow a broadly similar structure. Read against the estimates in Section 6.1, the \$4,000 ceiling appears to matter for only a narrow part of the market. It is comparable to the residual valuation gap for high-budget car buyers considering longer-range vehicles, the segment already closest to parity, but appears far below what other segments would require: roughly \$8,000–\$13,000 to close the gap on a 100-mile used BEV in the car segment and \$16,000–\$19,000 in the SUV segment, and \$4,000–\$12,000 even for a 300-mile BEV.

The design of the credit also appears to disfavor the most responsive segment. The \$25,000 price cap excludes most used BEVs with 250–300 miles of range, the configuration for which WTP reaches conventional-vehicle parity among high-budget car buyers, while directing support toward shorter-range vehicles whose valuation gap \$4,000 cannot close; applied instead to the near-parity segment, an unconditioned subsidy would risk mostly rewarding purchases that would likely have occurred anyway. Consistent with Roberson and Helveston (2022), incentive structure appears to matter as much as magnitude: buyers are reported to value immediate rebates well above equivalent tax credits, and that premium appears largest for the lower-income, lower-budget, and used-vehicle buyers who dominate this market. The estimates also point toward non-price instruments. About \$15,000–\$20,000 of the WTP difference between a two- and an eight-year-old BEV exceeds conventional depreciation and most plausibly reflects uncertainty about battery

state of health; measures that make battery condition observable, such as a standard health report at listing or warranty cover that transfers on resale (Li et al., 2020), target the likely source of that discount and would plausibly cost less in public funds than a point-of-sale subsidy. The comparison between simulated WTP and observed real-market pricing in Section 6.2 reinforces this point: used-BEV listings in the matched pairs examined are priced at premiums of roughly \$6,100 to \$16,900 above what our WTP estimates imply consumers would accept, suggesting that used-BEV pricing has not yet adjusted downward to reflect the discount buyers appear to require – a gap that demand-side incentives targeted at the point of sale could help close more directly than reliance on natural market repricing alone. Because the BEV valuation gap closes to statistical parity only for high-budget car buyers at long range, while HEV powertrains already carry a positive WTP premium over their real-world conventional counterparts among high-budget car and SUV buyers (Section 6.2), the results appear to favor segment-aware policy: point-of-sale incentives for BEVs targeted by vehicle age and range, paired with continued support for HEV adoption where it is already market-competitive and with measures intended to close the battery-health information gap.

8. Conclusion

Driving range and mileage appear to be the dominant value determinants, each producing WTP effects that substantially exceed those attributable to budget tier or vehicle segment alone: electric range is valued at approximately \$2,200 to \$5,200 per 100 miles and mileage at approximately \$1,000 to \$3,800 per 10,000 miles, compared with \$300 to \$2,200 per year of vehicle age and \$400 to \$1,100 per cent-per-mile of operating cost. The only segment and budget combination for which BEV WTP appears to reach statistical parity with the conventional baseline is high-budget car buyers selecting 300-mile-range vehicles. For all other combinations considered, used BEVs would need to be offered at a discount, with the required discount scaling most strongly with declining range and increasing mileage, and to a lesser extent with vehicle age and operating cost. HEV powertrains, by contrast, already command real-market price premiums broadly consistent with – or, in the high-budget car segment, below – what our WTP estimates imply consumers would accept, whereas real-market BEV price premiums exceed the WTP-implied requirement for competitiveness in every matched pair examined.

Stated WTP for a used BEV falls below that for an equivalent conventional vehicle in nearly every segment and budget tier, and the gap closes only for high-budget car buyers choosing long-range vehicles. These results rest on a discrete choice experiment with 2,254 prospective used-vehicle buyers and six mixed logit models that capture heterogeneity across vehicle and budget segments.

Three findings appear to carry direct implications for used-BEV market development. First, the used-BEV market does not appear to have reached price parity with conventional vehicles for the majority of prospective buyers: only high-budget car buyers selecting 300-mile-range vehicles demonstrate WTP at or near the ICE-equivalent price, while all other segment and budget combinations would appear to require discounts ranging from modest to over \$35,000. Second, driving range and mileage are found to be the two largest attribute-level drivers of WTP across all segments, each carrying substantially greater dollar magnitude than vehicle age or operating cost (\$2,200–\$5,200 per 100 miles of range and \$1,000–\$3,800 per 10,000 miles of mileage, versus \$300–\$2,200 per year of age and \$400–\$1,100 per cent-per-mile of operating cost); a related market simulation that lets mileage accumulate jointly with age finds a combined WTP differential of \$15,000 to \$20,000 between a vehicle held for 2 years versus 8 years within a given segment, a gap exceeding standard ICE depreciation that most plausibly reflects consumer uncertainty about battery state-of-health compounding with both age and accumulated mileage, suggesting that interventions improving state-of-health transparency (standardized health disclosures, third-party certification, or extended manufacturer warranties in the secondary market) could recover a portion of this penalty without requiring changes to the vehicle itself. Third, a complementary comparison of simulated WTP against real-market prices for matched vehicle pairs indicates that observed used-BEV price premiums exceed what our WTP estimates imply is needed for parity with a conventional counterpart in every pair examined – by roughly \$6,100 for a high-budget car pair priced near parity, and by \$15,700–\$16,900 for two lower-budget pairs that are in fact priced at a premium over their conventional counterparts – while HEV powertrains already carry real-market price premiums that are comparable to, or in one case well below, the WTP-implied premium, suggesting hybrid adoption as a comparatively low-friction near-term substitute for full battery-electric adoption in the used market.

Three findings appear to carry direct implications for used-BEV market development. First, the used-BEV market does not appear to have reached price parity with conventional vehicles for the majority of prospective buyers: only high-budget car buyers selecting 300-mile-range vehicles demonstrate WTP at or near the ICE-equivalent price, while

all other segment and budget combinations would appear to require discounts ranging from modest to over \$35,000. Second, driving range and mileage are found to be the two largest attribute-level drivers of WTP across all segments, each carrying substantially greater dollar magnitude than vehicle age or operating cost (\$2,200–\$5,200 per 100 miles of range and \$1,000–\$3,800 per 10,000 miles of mileage, versus \$300–\$2,200 per year of age and \$400–\$1,100 per cent-per-mile of operating cost); a related market simulation that lets mileage accumulate jointly with age finds a combined WTP differential of \$15,000 to \$20,000 between a vehicle held for 2 years versus 8 years within a given segment, a gap exceeding standard ICE depreciation that most plausibly reflects consumer uncertainty about battery state-of-health compounding with both age and accumulated mileage, suggesting that standardized battery-health reporting could recover part of this penalty without changing the vehicle itself. Third, a complementary comparison of simulated WTP against real-market prices for matched vehicle pairs indicates that observed used-BEV price premiums exceed what our WTP estimates imply is needed for parity with a conventional counterpart in every pair examined – by roughly \$6,100 for a high-budget car pair priced near parity, and by \$15,700–\$16,900 for two lower-budget pairs that are in fact priced at a premium over their conventional counterparts – while HEV powertrains already carry real-market price premiums that are comparable to, or in one case well below, the WTP-implied premium, suggesting hybrid adoption as a comparatively low-friction near-term substitute for full battery-electric adoption in the used market.

The analysis rests on stated rather than revealed preferences, and because the WTP-space models scale every attribute by a single price parameter, any hypothetical bias in price sensitivity propagates into every WTP estimate; its direction in this context remains uncertain. The sample was drawn from online research panels and may over-represent respondents who are comfortable with new technology, which could bias BEV valuations upward. The MXL specification assumes continuous, unimodal normal mixing distributions, which may hide a distinct group of firm BEV rejecters (the large standard deviations on the BEV coefficient hint at this); a latent class extension would test this directly. The vehicle DCE’s powertrain attribute was limited to three levels – conventional, HEV, and BEV – and did not include a plug-in hybrid (PHEV) alternative; PHEV purchase likelihood was instead captured only through a separate Likert-scale item elsewhere in the survey, so the WTP estimates reported here cannot speak directly to how a PHEV option would be valued against the three powertrains compared in the choice tasks. Battery state-of-health was not varied in the vehicle-powertrain DCE analyzed here and is instead addressed in a companion battery DCE component of the broader study. Integrating findings from both instruments and cross-validating against revealed transaction prices from dealer records would likely strengthen the empirical basis for the policy inferences drawn above. The real-vehicle price comparison in Section 6.2 relies on a small number of matched pairs (three BEV-versus-CV, two HEV-versus-CV) evaluated at a single vehicle age (approximately three years) rather than across a range of ages; broader real-market coverage, additional matched pairs, and comparisons at multiple ages would strengthen confidence in the pricing-versus-WTP gaps reported there.

Future work could extend this design in several directions. Adding a fourth, plug-in-hybrid powertrain level to the vehicle DCE would allow WTP for PHEVs to be estimated directly and compared against the BEV and HEV valuations reported here, rather than inferred indirectly from the Likert-scale purchase-likelihood items. A latent-class or other discrete-mixture specification would test whether the heterogeneity captured by the normal random parameters in the current MXL models instead reflects a small number of distinct preference segments, which would carry different policy implications than continuous heterogeneity around a common mean. Fielding a parallel wave linked to revealed transaction data – for example, matching survey respondents’ subsequent purchases to dealer or DMV records – would allow the stated-preference WTP estimates reported here to be validated against actual used-vehicle choices. Finally, jointly estimating the vehicle-powertrain and battery-health DCE components administered in this survey within a single nested or integrated choice model, rather than analyzing them as separate instruments, would allow the battery state-of-health penalties documented in the companion battery paper to be combined directly with the age- and mileage-driven depreciation patterns identified here, yielding a unified WTP surface for used BEVs.

- FUTURE WORK: - Many information collected in the survey was not utilized in this study. The study can further segment individuals based on other variables.

CRediT authorship contribution statement

Zain Hoda: Conceptualization, Data curation, Methodology, Software, Formal analysis, Writing - Original Draft, Writing - Review & Editing. **Xiatian Iogansen:** Conceptualization, Data curation, Methodology, Writing - Review & Editing. **Christina Gore:** Conceptualization, Data curation, Methodology, Investigation, Writing - Original draft preparation, Writing - Review & Editing, Supervision, Project administration, Funding acquisition. **Joshua D. Kneifel:**

Conceptualization, Data curation, Methodology, Investigation, Writing - Review & Editing, Supervision, Project administration, Funding acquisition. **Sindhu Ranganath:** Data curation, Writing - Original Draft, Writing - Review & Editing. **John Helveston:** Conceptualization, Methodology, Writing - Review & Editing, Supervision.

References

- Brückmann, G., M. Wicki, and T. Bernauer (Nov. 2021). "Is Resale Anxiety an Obstacle to Electric Vehicle Adoption? Results from a Survey Experiment in Switzerland". In: *Environmental Research Letters* 16.12, p. 124027. ISSN: 1748-9326. DOI: 10.1088/1748-9326/ac3531. URL: <https://dx.doi.org/10.1088/1748-9326/ac3531> (visited on 06/30/2025).
- Bureau of Transportation Statistics (2023). *National Transportation Statistics*. Tech. rep. U.S. Department of Transportation, Bureau of Transportation Statistics. URL: <https://www.bts.gov/topics/national-transportation-statistics>.
- C-4 Analytics (2025). *2025 automotive consumer price sensitivity*. URL: <https://c-4analytics.com/insights/2025-automotive-consumer-price-sensitivity>.
- Canepa, K., S. Hardman, and G. Tal (June 1, 2019). "An Early Look at Plug-in Electric Vehicle Adoption in Disadvantaged Communities in California". In: *Transport Policy* 78, pp. 19–30. ISSN: 0967-070X. DOI: 10.1016/j.tranpol.2019.03.009. URL: <https://www.sciencedirect.com/science/article/pii/S0967070X18303524> (visited on 07/01/2025).
- Consumer Reports (2023). *Used Car Buying Guide*. URL: <https://www.consumerreports.org/cars/used-cars/buying-guide/>.
- Cox Automotive (2024). *Used vehicle retail listing prices decline in 2024*. URL: <https://www.coxautoinc.com/insights/used-vehicle-retail-listing-prices-decline-2024/>.
- (2025). *Cox Automotive car buyer journey study finds efficiency, digital tools and AI drive record satisfaction*. URL: <https://www.coxautoinc.com/insights/cox-automotive-car-buyer-journey-study-finds-efficiency-digital-tools-and-ai-drive-record-satisfaction/>.
- Fernandes, J. (2023). *US: Understanding Consumer Opinion about Used Electric Cars*. URL: <https://business.yougov.com/content/47834-us-understanding-consumer-opinion-about-used-electric-cars> (visited on 06/30/2025).
- Guzek, M., J. Jackowski, R. S. Jurecki, E. M. Szumska, P. Zdanowicz, and M. Zmuda (Jan. 2024). "Electric Vehicles—An Overview of Current Issues—Part I—Environmental Impact, Source of Energy, Recycling, and Second Life of Battery". In: *Energies* 17.1 (1), p. 249. ISSN: 1996-1073. DOI: 10.3390/en17010249. URL: <https://www.mdpi.com/1996-1073/17/1/249> (visited on 07/01/2025).
- Hagman, J., S. Ritzén, J. J. Stier, and Y. Susilo (Mar. 1, 2016). "Total Cost of Ownership and Its Potential Implications for Battery Electric Vehicle Diffusion". In: *Research in Transportation Business & Management*. Innovations in Technologies for Sustainable Transport 18, pp. 11–17. ISSN: 2210-5395. DOI: 10.1016/j.rtbm.2016.01.003. URL: <https://www.sciencedirect.com/science/article/pii/S2210539516000043> (visited on 07/01/2025).
- Helveston, J. (Oct. 20, 2025). *cbcTools: Design and Analyze Choice-Based Conjoint Experiments*. Version 0.7.1. URL: <https://cran.r-project.org/web/packages/cbcTools/index.html> (visited on 10/22/2025).
- Helveston, J. P. (Feb. 7, 2023). "Logitr: Fast Estimation of Multinomial and Mixed Logit Models with Preference Space and Willingness-to-Pay Space Utility Parameterizations". In: *Journal of Statistical Software* 105, pp. 1–37. ISSN: 1548-7660. DOI: 10.18637/jss.v105.i10. URL: <https://doi.org/10.18637/jss.v105.i10> (visited on 06/24/2025).
- Helveston, J. P., Y. Liu, E. M. Feit, E. Fuchs, E. Klampfl, and J. J. Michalek (2014). "Consumer Preferences for Hybrid and Electric Vehicles in China and the United States – Implications for Policy and Environment". In: *Transportation Research Board 93rd Annual Meeting*. Washington, D.C.
- Kelley Blue Book (Apr. 2025). *Average used car price rising, sales slowing*. URL: <https://www.kbb.com/car-news/average-used-car-price-rising-sales-slowing/>.
- Konstantinou, T., D. Chakraborty, and J. B. Gutierrez Lopez (2025). "Understanding the used vehicle market and its implications for electric vehicles". In: *Transportation Research Record: Journal of the Transportation Research Board* 2679.5, pp. 643–660. DOI: 10.1177/03611981241302336. URL: <https://journals.sagepub.com/doi/epub/10.1177/03611981241302336>.
- Li, L., Z. Wang, L. Chen, and Z. Wang (2020). "Consumer preferences for battery electric vehicles: a choice experimental survey in China". In: *Transportation Research Part D: Transport and Environment* 78, p. 102185. DOI: 10.1016/j.trd.2019.11.014. URL: <https://doi.org/10.1016/j.trd.2019.11.014>.
- Liao, F., E. Molin, and B. van Wee (2017). "Consumer preferences for electric vehicles: a literature review". In: *Transport Reviews* 37.3, pp. 252–275. DOI: 10.1080/01441647.2016.1230794. URL: <https://doi.org/10.1080/01441647.2016.1230794>.
- Lim, M. K., H.-Y. Mak, and Y. Rong (Feb. 2015). "Toward Mass Adoption of Electric Vehicles: Impact of the Range and Resale Anxieties". In: *Manufacturing & Service Operations Management* 17.1, pp. 101–119. ISSN: 1523-4614. DOI: 10.1287/msom.2014.0504. URL: <https://pubsonline.informs.org/doi/10.1287/msom.2014.0504> (visited on 06/30/2025).
- Loh, W. S. and R. B. Noland (2024). "Concerns expressed by used electric vehicle owners based on surveying social media". In: *Transportation Research Part D: Transport and Environment* 128, p. 104086. DOI: 10.1016/j.trd.2024.104086. URL: <https://doi.org/10.1016/j.trd.2024.104086>.
- Mashrur, S. M. and M. Mohamed (2025). "Uncovering factors affecting consumers' decisions for pre-owned electric vehicles". In: *Transportation Research Part D: Transport and Environment* 139, p. 104555. DOI: 10.1016/j.trd.2024.104555. URL: <https://doi.org/10.1016/j.trd.2024.104555>.
- Moras, B. C. K., C. M. Joslin, and K. Gkritza (2025). "Used or new electric vehicles? Public preferences and market segments". In: *International Journal of Sustainable Transportation* 20.1, pp. 129–142. DOI: 10.1080/15568318.2025.2572827. URL: <https://www.tandfonline.com/doi/full/10.1080/15568318.2025.2572827>.

- 1 Prieto, M., B. Caemmerer, and G. Baltas (2015). "Using a hedonic price model to test prospect theory assertions: the asymmetrical and nonlinear
2 effect of reliability on used car prices". In: *Journal of Retailing and Consumer Services* 22, pp. 206–212. DOI: 10.1016/j.jretconser.
3 2014.08.013.
- 4 Roberson, L. and J. P. Helveston (July 2022). "Not All Subsidies Are Equal: Measuring Preferences for Electric Vehicle Financial Incentives". In:
5 *Environmental Research Letters* 17.8, p. 084003. ISSN: 1748-9326. DOI: 10.1088/1748-9326/ac7df3. URL: [https://doi.org/10.](https://doi.org/10.1088/1748-9326/ac7df3)
6 [1088/1748-9326/ac7df3](https://doi.org/10.1088/1748-9326/ac7df3) (visited on 01/23/2026).
- 7 Rosales-Tristancho, A., A. F. Carazo, R. Brey, and H. Lindhjem (2024). "Meta-analysis of consumers' trade-offs between range and charging
8 infrastructure for electric vehicles". In: *Transportation Research Part D: Transport and Environment* 134, p. 104342. DOI: 10.1016/j.trd.
9 2024.104342. URL: <https://doi.org/10.1016/j.trd.2024.104342>.
- 10 Shaikh, W. A., M. A. Kalwar, M. A. Khan, A. N. Wassan, M. H. Wadho, and M. F. Shahzad (2023). "A System Dynamics Costing Model for The
11 Refurbishment of Electric Vehicle Batteries". In: *Jordan Journal of Mechanical and Industrial Engineering* 17.01, pp. 15–32. ISSN: 1995-6665,
12 1995-6665. DOI: 10.59038/jjmie/170102. URL: <http://jjmie.hu.edu.jo/vol17/vol17-1/02.htm> (visited on 07/02/2025).
- 13 Sheykhfard, A., M. Azmoodeh, S. Das, and B. Kutela (Jan. 1, 2025). "Analyzing Purchase Intentions of Used Electric Vehicles through Consumer
14 Experiences: A Structural Equation Modeling Approach". In: *Transport Policy* 160, pp. 125–137. ISSN: 0967-070X. DOI: 10.1016/j.
15 tranpol.2024.10.038. URL: <https://www.sciencedirect.com/science/article/pii/S0967070X24003305> (visited on
16 07/01/2025).
- 17 Sk. Md. Mashrur, M. M. (2024). "Uncovering factors affecting consumers' decisions for pre-owned electric vehicles". In: *Transportation Research*
18 *Part D: Transport and Environment*. High-income, full-time-employed owners with private parking more likely to buy used EVs; charging
19 infrastructure and price concerns as barriers. URL: <https://www.sciencedirect.com/science/article/pii/S1361920924005121>.
- 20 U.S. Environmental Protection Agency (2023). *Light-Duty Automotive Technology, Carbon Dioxide Emissions, and Fuel Economy Trends*. Tech. rep.
21 U.S. Environmental Protection Agency, Office of Transportation and Air Quality. URL: [https://cfpub.epa.gov/si/si_public_file_](https://cfpub.epa.gov/si/si_public_file_download.cfm?Lab=0TAQ&p_download_id=499454)
22 [download.cfm?Lab=0TAQ&p_download_id=499454](https://cfpub.epa.gov/si/si_public_file_download.cfm?Lab=0TAQ&p_download_id=499454).
- 23 Wei San Loh, R. B. N. (2024). "Concerns expressed by used electric vehicle owners based on surveying social media". In: *Transportation Research*
24 *Part D: Transport and Environment*. Used-EV owner demographics: disproportionately male, middle-aged, well-educated, higher-income. URL:
25 <https://www.sciencedirect.com/science/article/pii/S1361920924000439>.
- 26 Zou, T., M. Khaloei, and D. MacKenzie (2020). "Effects of charging infrastructure characteristics on electric vehicle preferences of new and used
27 car buyers in the United States". In: *Transportation Research Record: Journal of the Transportation Research Board* 2674.12, pp. 165–175.
28 DOI: 10.1177/0361198120952792. URL: <https://journals.sagepub.com/doi/10.1177/0361198120952792>.